



Rogers Pump Sales & Service Inc.

16 South Washington Avenue
Batavia, IL 60510

ESTIMATE	#76550
ESTIMATE DATE	Feb 14, 2026
EXPIRATION DATE	Mar 30, 2026
DEPOSIT DUE	\$25,120.75

McHenry County Government
2200 N Seminary Ave
Woodstock, IL 60098

SERVICE ADDRESS
2406 Hartland Rd
Woodstock, IL 60098

(815) 334-0105
DWLittle@mchenrycountyil.gov

CONTACT US
(630) 879-7747
scheduling@rogerspump.com

ESTIMATE

Services	qty	unit price	amount
Labor - Removal and Installation	1.0	\$5,400.00	\$5,400.00
INCLUDED: - Remove existing fire pump controller - Install new fire pump controller - Remove existing jockey pump controller or HOA - Install new jockey pump controller - Disconnection and re-connection of all electrical too include fire alarms - Disconnection and re-connection of sensing lines - Programming and startup of new controllers **Service to be completed during normal business hours: 7 a.m. - 3 p.m.** EXCLUSIONS: - Labor for installation after hours or weekend - ComEd disconnect fee if applicable - Fire watch if applicable - Added cost for tariffs if applicable - Permit application			
Acceptance Test	1.0	\$600.00	\$600.00
Acceptance Fire Pump Test			
EXPEDITE FEES	1.0	\$650.00	\$650.00
15 WORKING DAY DOES NOT INCLUDE TRANSIT TIME			

Services subtotal: \$6,650.00

Materials	qty	unit price	amount
GPS+GPU-208/40/3/60	1.0	\$24,305.75	\$24,305.75
Fire Pump Controller Soft Start Soft Stop			
CUSTOM BUILD WITH ATS ON LEFT SIDE			
Built in Automatic Transfer Switch			
- Surge suppression - Disconnecting means Single operator for both isolating switch and circuit breaker Door interlocked in the ON position - Suitable as service entrance equipment - Emergency start handle - Locked rotor protector Voltage and amperage display			

Cut-in, cut-out and continuous system pressure readings

- Visual indications:

Standard Conditions

Alarm Conditions

Color coded for criticalness

-Remote alarm contacts (DPDT-8A-250V.AC)

Power available

Phase reversal

Motor run

Common pump room alarm (field re-assignable)

Common Motor trouble (field re-assignable)

Free (field programmable)

JPLT-208/0.5/3/60

1.0

\$815.00

\$815.00

Jockey Pump Controller

1/2HP

208VAC

3 PH

HP rated fuse-less thru-the-door main disconnect switch.

iPD+ Operator Interface provides

Visual indicators

Manual motor run

Automatic motor run

System pressure

Automatic mode

Off mode

Motor overload

Pump start counter

Elapsed time meter (hours / non-resettable)

All adjustments on door front

Timers

Minimum run period timer

Sequential start timer

Operators

OFF-AUTO pushbutton

Start and stop pushbuttons.

Controller Sensing Line Kit

2.0

\$675.00

\$1,350.00

(2) 1/2" Ball Valves

(1) 1/2" Brass Tee

(1) 1/2" x 1/2" x 1/4" Brass Tee

(4) 1/2" x 1 1/2" Brass Nipple

(1) 1/2" Brass Plug

(1) 3 1/2" Pressure Gauge

(2) Brass 1/2" Orifice Union

1/2" Copper/Brass Piping

Electrical

1.0

\$1,200.00

\$1,200.00

- Misc. Water Tight Fittings & Hubs

- Conduit

- Alarm wiring

- Wire to Motor

- Wire to Fire Pump Controller

- Junction Box NEMA 2

- UL Listed Splice Connections

Materials subtotal: \$27,670.75

Subtotal

\$34,320.75

Total

\$34,320.75

Deposit

\$25,120.75

Your business is greatly appreciated.